

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22347-00-00  
Spot: CE2E2NW Sec/Twnshp/Rge: 26-13S-20W  
3960 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: ZIMMERMAN Well Number: 5  
County: ELLIS Total Vertical Depth: 3825 feet

Operator License No.: 101  
Op Name: KCC FEE FUND  
Address: 130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 168 w/135 sxs cmt  
Production: Size 5.5 feet: 3817 w/150 sxs cmt  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/05/2001 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC  
Proposal Rcvd. from: DUANE ACHTERBERG Company: FLATLAND MAINTENANCE SERVI Phone: (785) 635-7335

Proposed Plugging Method: Ordered out 240 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/05/2001 10:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:


RIH tubing with bit - hit hard bridge at 400'.  
Drilled out to 750' - got outside of the casing. Decided to P&A.  
RIH with tubing to 750' - tied onto and circulated cement with 100 sxs .  
POOH. Tied onto 5 1/2" and topped with 140 sxs and 500# hulls.  
Max. P.S.I. 1250# S.I.P. 900#.  
Annulus full of cement.

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

RECEIVED

NOV 13 2001

KCC WICHITA

NOV 06 2001

