

1060541

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-22,681-0000  
SW NW SE, SEC. 31, T 17 S, R 25 W/XX

1330 feet from S section line  
2000 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9289

Lease Name C. Barrows Well # 1

Operator: Walter Oil & Gas Corporation  
Name & Address: 240 Main Building,  
1212 Main Street  
Houston, TX 77002

County Ness 142.03  
Well Total Depth 4370 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 351 ✓

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Services License Number \_\_\_\_\_

Address P. O. Box 579, Great Bend, KS 67530

Company to plug at: Hour: 10:00 am Day: 12 Month: April Year: 1985

Plugging proposal received from Mack MacDougal

(company name) Walter (phone) 713-659-1221

were: 4 1/2" at 4365-cement circulated PBD 3995' Perfs at 3752-56'

1st plug pump 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release

8 5/8" rubber plug and pump 5 sx cement.

2nd plug pump annulus with 20 sx cement.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 11:20 am Day: 12 Month: April Year: 1985

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 5 sx cement. Maximum pressure 2500 psi and shut in 2000 psi. 2nd plug pumped annulus with 20 sx cement. Maximum pressure 300 psi and shut in 300 psi.

RECEIVED  
STATE CORPORATION COMMISSION

APR 23 1985

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: No recovery. Used 60/40 Pozmix 2% gel 3% cc by Halliburton  
(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

Signed Paul A. Luthi  
(TECHNICIAN)

DATE 5-6-85

INV. NO. 7950