

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

RECEIVED  
STATE CORPORATION COMMISSION

DEC 26 1973

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Norwood of DNB Drlg. has this

date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Bankoff Oil Co.

Complete Address: Drawer 2479 Tulsa, Okla.

Lease Name: Popp ~~XX~~ "A" Well No. 1

Location: C NE NW Sec. 30 Twp. 17 Rge. (E)(W) 25

County: Ness Total Depth 4460' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Norwood was instructed to plug the well as follows:

Grp pits, circulate heavy mud, set cementing plug at 720' and displace

70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Mussey  
Conservation Division Agent