



15-135-20910-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Thorpe of Gabbert-Jones Drlg. has this

date requested permission to plug the following described well:

Mr. Thorpe guarantees payment of the plugging fee.

Operator's full Name: Beren Corporation

Complete Address: 1130 Vickers KSB&T Bldg., Wichita, Ks.

Lease Name: Popp Well No. 1

Location: C NE NW Sec. 29 Twp. 17 Rge. (E)(W) 25

County: Ness Total Depth 4440' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Thorpe was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace
70 sk cmt thru drill pipe. Heavy mud to 215' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

[Signature]
Conservation Division Agent