



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

RECEIVED  
STATE CORPORATION COMMISSION

MAR 25 1972

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Clem Burton of Pickrell Drilling Company has this  
date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company,

Complete Address: 705 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Norton-Reed Well No. A-1

Location: CNW-SW Sec. 29 Twp. 17 Rge. (E)(W) 25

County: Ness Total Depth 4468' Oil Well Y

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Burton was instructed to plug the well as follows:

258'--8 5/8" Surface casing, cement circulated with 140 Sx.  
Top of Dakota section @ 500':

Circulate hole with heavy mud. Pull DP to 725' and displace 110 Cu. Ft.  
cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP.  
Pull DP, set bridge @ 40" with 1/2 sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

Conservation Division Agent