



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Robert Fowler of Lynn Drilg. has this date requested permission to plug the following described well:

Operator's Full Name: Petco Venture
Complete Address: 4704 Harlan #600 Denver, Colorado 80202

Lease Name: Sidwell Well No. #1
Location: SE-NE-SW Sec. 2 Twp. 17 Rge. 26 (E) (W)
County: Wes Total Depth: 4775 ET

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Fowler was instructed to plug the well as follows:

8 5/8" 324 ET SP. cur w/ 190ST Class A - 226el - 226el
Order 115ST 50/50 Pozmix 6% Gel + 8 5/8" Plug
spot with Drill Stem - with heavy mud between all Plugs
1ST Plug - 65ST @ 1200 ET
2ND Plug - 30ST @ 360 ET
3RD Plug - 10ST solid Bridge Sulls Plug @ 40^{ET} to
5TH In Rat Hole
5TH In Mouse Hole

Very truly yours, (By Wellington Cant)

Marion Schmidt
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1981
CONSERVATION DIVISION
Wichita, Kansas