

State of Kansas



15-135-20012-00-011

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1967
02-15-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Baker of NCRA has this

date requested permission to plug the following described well:

Mr. Baker guarantees payment of the plugging fee.

Operator's full Name: National Cooperative Ref. Ass.

Complete Address: P. O. Box 6 Great Bend, Kansas

Lease Name: Irvin Well No. 1

Location: C SE SE Sec. 1 Twp. 17 Rge. 21 (E)(W) X

County Ness Total Depth 4100' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Baker was instructed to plug the well as follows:

Gun pits, Circulate heavy mud, set cementing plug at 600' and displace
25 sc cement thru drill pipe, Heavy mud to 400' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Conservation Division Agent