

15-135-20423-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ness County, Sec. 2 Twp. 17 Rge. 26 (E) W (W)
Location as "NE/CNW&SW" or footage from lines C NW SE
Lease Owner Pickrell Drlg. Co.; Wichita, Kans. 67202
Lease Name Dumler Unit Well No. #7
Office Address 205 Fourth Nat'l Bank Building
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed April 3 19 71
Application for plugging filed April 19 73
Application for plugging approved April 19 73
Plugging commenced April 5 19 73
Plugging completed May 16 19 73
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production January 25 19 73
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Miss. Depth to top 4476 Bottom 4490 Total Depth of Well 4490 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Miss.	Oil	4476	4490	8 5/8"	241	None
				5 1/2"	4482	3044

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

April 5, 1973 Plugged off bottom. Dumped sand to 4350". Mixed and dumped 5 sx of cement.

May 16, 1973 Mixed and pumped down 8 5/8" surface casing; 25 sx of gel with 5 sx of hulls, 70 sx of cement, 10 sx of gel, released plug and 50 sx of cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 31 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor RUSS CASING PULLING, INC.
Address P. O. Box 1082 ; Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF SEDGWICK ss.
Jack Gurley (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack Gurley
Jack Gurley
705 Fourth National Bank Bldg., Wichita, Ks.
(Address)



SUBSCRIBED AND SWORN to before me this 30th day of May, 19 73
Helen L. Sage
Helen L. Sage Notary Public.

copy mailed
WLB 3/25/71

15-135-20423-0000

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 3/11/71
Rotary Drilling Completed 3/20/71

LOCATION: Dumler Unit No. 7, 920' from the North Line, 1800' from the East Line
of the SE/4 Section 2-17S-26W, Ness County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Run 11 Jts. 8-5/8" surface casing set @ 241' K.B. Cemented with
150 Sacks. Completed 9:30 P.M. March 11, 1971. Circulated.

Ran 133 Jts. 5-1/2" Casing set @ 4482' K.B. Cemented with 125 sacks
50-50 Pozmix 4% gel followed by 50 sacks common. Plug down 5:00 A.M.
March 20, 1971.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

241	Shale & Shells		<u>C.F.S.</u>
775	Shale		4490
1315	Red Beds - Shale		
1340	Blaine		
1410	Shale & Shells		
1715	Sand - w/Shale Streaks		<u>S.L.M.</u>
1926	Shale		
1958	Anhydrite	Board	3722.65
2400	Red Bed & Shale w/Lime	Strap	<u>3720.96</u>
2596	Shale - Lime		1.69 Difference
3150	Lime - Shale		
3500	Shale & Lime		
3665	Lime - Shale		<u>Slope Tests</u>
3865	Shale & Lime		2000
4490	Lime, RTD		2500
			3000
			3500
			4000

RECEIVED
STATE CORPORATION COMMISSION
APR 3 1973
CONSERVATION DIVISION
Wichita, Kansas


The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY,
hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling
the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 25th day of March, 1971, before me the undersigned, a Notary Public, in and for
County and State aforesaid, personally appeared C. W. Sebitts, to me known to
be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its
Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free
and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.



My commission expires: January 19, 1973

[Signature]
Esther Lamone Notary Public