

15-135-20564-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH

Ness County, Sec. 3 Twp. 17S Rge. XX 26 (W)
Location as "NE/CNWxSWx" or footage from lines C NE SE
Lease Owner Pickrell Drilling Company
Lease Name Dumler "N" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 27 19 72
Application for plugging filed January 27 19 72
Application for plugging approved January 27 19 72
Plugging commenced January 27 19 72
Plugging completed January 27 19 72
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4590 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	257	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug @ 800' w/70 sacks, Middle Plug @ 240' w/20 sacks, Top Plug @ 40' w/10 sacks

RECEIVED
STATE CORPORATION COMMISSION
FEB 3 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Kansas
(Address)

Subscribed and sworn to before me this 1st day of February, 19 72
January 19, 1973
My commission expires _____
Esther Lamone
Notary Public.



ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 1/19/72

Rotary Drilling Completed 1/27/72

LOCATION: Dumler "N" No. 1, C NE SE Section 3-17S-26W
Ness County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Run 6 jts. 8-5/8" surface casing set @ 257' KB. Cemented
w/150 sacks. Completed 3:15 P.M. Circulated.

No oil string run. D & A. Plugged down 9:30 P.M. January 27, 1972.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

50	Surface Soil Sand	<u>C.F.S.</u>
130	Clay & Post Rock	None
680	Shale & Sand Streaks	
720	Sand	
1405	Shale	
1430	Blaine	
1500	Shale - Red Beds	
1760	Sand	
1830	Shale - Red Beds	<u>Slope Tests</u>
2008	Shale	2000
2035	Anhydrite	2500
2330	Shale & Lime	3000
2605	Lime	3500
2720	Lime & Shale	4000
3360	Lime	4500
3485	Lime - Shale	
3555	Shale & Lime	
3815	Lime - Shale	
3945	Shale & Lime	
4590	Lime - Miss., RTD	

RECEIVED
STATE CORPORATION COMMISSION
FEB 3 1972
CONSERVATION DIVISION
Wichita, Kansas

C. W. Sebitts

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.


PICKRELL DRILLING COMPANY
By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 1st day of February, 19 72, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to

be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact, and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.



My commission expires: January 19, 1973

Esther Lamone
Notary Public