

15-135-20063-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ness County. Sec. 2 Twp 17S Rge. (E) 21(W)  
Location as "NE/CNW&SW" or footage from lines C S/2 NE/4

Lease Owner Chief Drilling Co., Inc.

Lease Name ELMORE "C" Well No. 1

Office Address Box 797 - Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9/21 1967

Application for plugging filed 9/21 1967

Application for plugging approved 9/21 1967

Plugging commenced 9/21 1967

Plugging completed 9/21 1967

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey - Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4130 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	412	8-5/8"	412	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Wooden plug set @ 660'  
Mixed 65 sx cement thru drill pipe  
Wooden plug set @ 390'  
Mixed 25 sx cement thru drill pipe  
Hull & plug set @ 40'  
Mixed 10 sx cement thru drill pipe


RECEIVED  
SEP 25 1967  
09-25-1967  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Chief Drilling Co., Inc. (If additional description is necessary, use BACK of this sheet)  
Address Box 797 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. Richard Hoover  
Box 797 - Great Bend, Kansas 67530 (Address)

Subscribed and sworn to before me this 22nd day of September, 1967



12, 1970

Carmen R. Cook, Notary Public.

15-135-20043-00-00-00

WELL LOG

Chief Drilling Co., Inc.  
Box 797  
Great Bend, Kansas 67530

ELMORE "C" #1  
C S/2 NE/4 Sec. 2-17S-21W  
Ness County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 9-12-67  
Completed: 9-21-67

Casing Record: 8-5/8" @ 412' w/225 sacks 60/40 Pozmix.

DRY & ABANDONED

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface Clay	0	110	2187 Gr.
Shale	110	268	2189 D.F.
Shale & Sand Streaks	268	335	2192 K.B.
Shale & Shells	335	500	
Shale w/Sand Streaks	500	730	
Shale	730	910	
Sand	910	1135	
Shale	1135	1205	
Shale & Shells	1205	1456	
Anhydrite	1456	1491	
Shale & Shells	1491	2020	
Shale	2020	2230	
Shale & Lime	2230	2505	
Lime	2505	2630	
Lime & Shale	2630	3280	
Lime	3280	3578	
Lime & Shale	3578	3622	
Lime	3622	3918	
Shale & Lime	3918	3964	
Lime & Chert	3964	4043	
Shale & Lime	4043	4066	
Sand & Shale	4066	4120	
Chert & Shale	4120	4130	
Total Depth (Rotary)	4130		

LOG TOPS

Heebner	3578	-1386
Toronto	3598	-1406
Lansing	3622	-1430
Base KC	3917	-1725
Pawnee	3964	-1772
Ft. Scott	4056	-1864
Cherokee	4066	-1874
T.D.	4124	-1932

RECEIVED  
STATE CORPORATION COMMISSION

SEP 25 1967

09-25-1967  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C S/2 NE/4 Section 2-17S-21W, Ness County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*V. Richard Hoover*  
V. Richard Hoover, President

Subscribed and sworn to before me this 22nd day of September, 1967.

*Carmen R. Cook*  
Carmen R. Cook, Notary Public

My commission expires: Dec. 12, 1970

