

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH

Elmore # 1 NE-NE-NW Sec. 2 17S, 21W Ness County, Kansas		

Locate well correctly on above
Section Plat

Ness County. Sec. 2 Twp 17S Rge. 21 W. (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE-NE-NW
Lease Owner Heathman and Company
Lease Name Elmore Well No. #1
Office Address 254 No. Washington Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-18 19 52
Application for plugging filed 5-18 19 52
Application for plugging approved 5-18 19 52
Plugging commenced 5-18 4:00 P. M. 19 52
Plugging completed 5-18 12:00 P. M. 19 52
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Verbal

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 4307 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Soil & Shale		0	156'		8 5/8	None
K. C. Lansing		3634'	4190'		Dry	Dry
Arbuckle		4190'	4307'		Dry	Dry
Total Depth		4307'				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Stirred Pitts well, filled hole with heavy mud to 180 feet. Set bottom wood plug. Ran 1/2 hulls and 15 sacks on same. Filled hole with heavy mud to 35 feet. Ran ;/2 sack hulls and 10 sacks cement, filling to bottom cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strain Drilling Company
Address Box 188, Hays, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.
T. C. Strain (employee of owner) or (owner or operator) of the above described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. T. C. Strain

(Signature)

Box 188, Hays, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 19 day of May, 19 52

MAY 21 1952
W. H. Schneider
Notary Public.

My commission expires March 26, 1956

23-8390-s

CONSERVATION DIVISION
Wichita, Kansas

05-21-1952

PLUGGING
FILE SEC 2 T 17 R 21W
BOOK PAGE 12 LINE 2

15-135-00194-00-00

WELL LOG

COMPANY: Heathman & Company

NE-NE-NW Sec. 2
Twp. 17S, Rge 21W
Ness County, Kansas

LEASE: Elmore # 1

ELEVATION: 2201 D. F.

NOTE: All meas Rotary Bushings

0	60 Blue Shale	3919	3970 Cherty Lime
60	223 Blue Shale	3970	4006 Cherty Lime
223	670 Shale, grey lime & Hard Sand	4006	4035 Lime & Shale & Chert
670	700 Sand & Pyrite	4035	4070 Lime & Chert & Shale
700	800 Shale & Redbed	4070	4099 Lime & Shale & Chert
800	1103 Sand	4099	4117 Lime & Shale
1103	1315 Shale & Redbed	4117	4155 Lime & Shale
1315	1481 Shale & Redbed	4155	4159 Chert
1481	1518 Anhydrite	4159	4180 Chert & Shale
1518	1670 Shale & Shells	4180	4208 Chert & Shale
1670	1885 Shale & Shells	4208	4265 Lime & Shale
1885	2110 Shale & Shells	4265	4307 Lime & chert
2110	2140 Shale & Shells	4307	(Total Depth) R. B.
2140	2260 Lime & Shale		
2260	2420 Lime & Shale		
2420	2475 Lime		
2475	2565 Lime		
2565	2615 Shale & Lime		
2615	2640 Shale & Sand		
2640	2745 Shale & Shells		
2745	2890 Shale & Lime		
2890	2990 Shale & Lime		
2990	3175 Shale & Shells		
3175	3285 Shale & Shells		
3285	3380 Lime & Shale		
3380	3446 Lime		
3446	3505 Lime		
3505	3620 Lime & Shale		
3620	3634 Lime & Shale		
3634	3675 K. C. Lime		
3675	3713 Lime		
3713	3755 Lime		
3755	3815 Lime		
3805	3826 Lime		
3826	3848 Lime		
3848	3875 Lime		
3875	3919 Lime		

COMMENCED: 5-3-52
COMPLETED: 5-18-52

Casing Record:
8 5/8" Surface Casing set at 156' w/100 sacks of cement by Globe Cementing Co.

D. S. T. by Johnston Testers
4049-4117 Toolopen 45 Min. B.H .P. 15
Recovered 2610' Salt Water. B.H.P. 1120#

No Electric Log Run

TOPS: Geologist Tops. Bob Armstrong

Heebner	3592	Marmaton Chert	3994
Toronto	3616	Cherokee	4057
K. C. Lansing	3634	Cherty Cong	4155
Base K. C.	3925	Arbuckle	4190

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1952
05-21-1952
CONSERVATION DEPARTMENT
WICHITA, KANSAS

STATE OF KANSAS) SS
COUNTY OF ELLIS)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Elmore # 1, located NE-NE-NW, Sec. 2, Twp. 17S, Rge 21W, Ness County, Kansas



PLUGGING
FILE SEC 2 T 17 R 21W
BOOK PAGE 17 LINE 2

CONTRACTOR Strain Drilling Co.
By. T. C. Strain
T. C. Strain

Subscribed and sworn to before me this 19 th day of May 1952.

My Commission expires March, 26 19. 56
M. D. Schneider
Notary Public