

15-135-20036-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Ness County, Sec. 2 Twp. 17 Rge. 21 (E) (W) X

Location as "NE/CNW/SW" or footage from lines C/NE/SE

Lease Owner Chief Drilling Co., Inc.

Lease Name Elmore "A" Well No. 1

Office Address 905 Century Plaza Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 1973

Application for plugging filed October 11, 1973

Application for plugging approved 1973

Plugging commenced October 12, 1973

Plugging completed October 13, 1973

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 1973

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 4150 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	402	-0-
				5 1/2	4149	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped sand to 4000' and dumped 5 sacks cement. Mudded hole to 550' and built a rock bridge to 500'. Plugged well with 3 yds. readymix concrete to surface.

RECEIVED  
STATE CORPORATION COMMISSION  
10-25-1973  
OCT 25 1973  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

Address P. O. Box 698 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss. James W. Rockhold

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

CATHY MILLER  
NOTARY PUBLIC  
Barton County, Ks.

(Signature) James W. Rockhold  
Box 698 Great Bend, Ks. 67530 James W. Rockhold  
(Address)

Subscribed and sworn to before me this 24th day of October, 1973

My commission expires September 30, 1975 Cathy Miller Notary Public.

15-135-20036-00-00

WELL LOG

RECEIVED  
STATE CORPORATION COMMISSION

OCT 15 1973  
10-15-1973  
CONSERVATION DIVISION  
Wichita, Kansas

Chief Drilling Co., Inc.,  
Box 797  
Great Bend, Kansas 67530

ELMORE "A" #1  
C NE SE Sec. 2-17S-21W  
Ness County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 6-5-67  
Completed: 6-16-67

Casing Record: 8-5/8" @ 402' w/225 sacks 60/40 Pozmix  
5-1/2" @ 4149' w/150 sacks 60/40 Pozmix - bottom 450  
sacks 50/50 Pozmix, 6% Jel

FORMATION	FROM	TO	ELEVATION	FORMATION TOPS	
			2177 Gr.		
			2179 D.F.		
			2182 K.B.		
				SAMPLE	LOG
Clay	0	130			
Shale	130	255			
Shale & Sand Streaks	255	330			
Shale	330	865			
Sand	865	1130			
Shale & Red Bed	1130	1451			
Anhydrite	1451	1485			
Shale & Shells	1485	2110	Anhydrite	1451	3567 -1385
Shale & Lime Streaks	2110	2170	Heebner	3569	
Lime & Shale	2170	2360	Toronto	3589	3586 -1404
Lime	2360	2470	Douglas	3603	
Lime & Shale	2470	2565	Lansing	3612	3611 -1429
Lime	2565	2642	Base K.C.	3898	
Lime & Shale	2642	3300	Pawnee	3959	3956 -1774
Lime	3300	3569	Ft. Scott	4042	4043 -1861
Lime & Shale	3569	3612	Cherokee Shale	4055	4053 -1871
Lime	3612	3898	1st Cherokee Sand		4055 -1873
Lime & Shale	3898	3959	Conglomerate		4095 -1913
Lime & Chert	3959	4055	Mississippi	4122	4118 -1936
Shale	4055	4057	Total Depth	4150	4148 -1966
Sand	4057	4094			
Conglomerate	4094	4118			
Chert & Dolomite	4118	4150			
Total Depth	4150				

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C NE SE Section 2-17S-21W, Ness County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.  
*V. Richard Hoover*  
V. Richard Hoover, President



Subscribed and sworn to before me this 20th day of June, 1967.

*Carmen R. Cook*  
Carmen R. Cook, Notary Public

My commission expires: Dec. 12, 1970