

15-135-20079-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 1 Twp. 17 S. Rge. 21 (W)  
Location as "NE/CNW/SW" or footage from lines C SW/4 NW/4  
Lease Owner: McKnab Production Company, Inc.  
Lease Name Lester V. Irvin Well No. 1  
Office Address 1028 Midland Savings Bldg., Denver, Colorado 80202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 9, 1967  
Application for plugging filed November 9, 1967  
Application for plugging approved November 9, 1967 (by phone) X X X  
Plugging commenced November 9, 1967 X X X  
Plugging completed November 10, 1967 X X X  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production == 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - by phone

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation == Depth to top Bottom Total Depth of Well 4140 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 720' from surface; set plug and 100 sacks cement.  
Filled hole to 390' with mud; set plug and 25 sacks cement.  
Filled hole to 40' with mud; set plug and 10 sacks cement.  
Filled rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 16 1967  
11-16-1967  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Halliburton Company  
Address P. O. Box 339, Hays, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. for  
F. S. Woodside, Jr., contractor, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. S. Woodside, Jr.  
427 Union Center, Wichita, Kansas 67202  
(Address)

Subscribed and sworn to before me this 10th day of November, 1967

Mary L. Lawrence  
Notary Public

My commission expires February 28, 1971

15-135-20079-00-00

ROTARY DRILLING LOG

Operator: McKnab Production Company, Inc.  
Lester V. Irvin #1  
SW/4 NW/4 1-17S-21W  
Ness County, Kansas

Contractor: Omega Drilling, Inc.

Commenced: October 31, 1967  
Completed: November 10, 1967

Casing Record: 8 5/8" surface casing  
cemented at 386' with  
250 sacks cement.

FORMATIONS

387	Surface clay
860	Clay and shale
1130	Sand
1438	Sand and shale
1471	Anhydrite and shale
1630	Shells and shale
2156	Shale and sand
2414	Shale and shells
2448	Shale and lime
2574	Lime
2721	Lime and shale
2885	Shale
3730	Shale and lime
3935	Lime
3977	Lime and chert
4004	Chert and shale
4140	Chert and lime

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 16 1967  
11-16-1967  
CONSERVATION DIVISION  
Wichita, Kansas

We certify that the above log is true and correct to the best of our knowledge and belief.

OMEGA DRILLING, INC.

By F. S. Woodside, Jr.  
F. S. Woodside, Jr.  
President

Subscribed and sworn to before me, a Notary Public, in and for the State of Kansas, County of Sedgwick, this 10th day of November, 1967.

Mary L. Lawrence  
Mary L. Lawrence, Notary Public



My commission expires February 28, 1971.