


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-135-00104-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 1 Twp. 17S Rge. 21 (X) W (W)
Location as "NE/CNW%SW%" or footage from lines NW NW SW
Lease Owner The Vickers Petroleum Co., Inc.
Lease Name Irvin Well No. 1
Office Address Box 2240, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed March 12, 19 56
Application for plugging filed March 12, 19 56
Application for plugging approved March 12, 19 56
Plugging commenced March 12, 19 56
Plugging completed March 12, 19 56
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. R. M. Brundage, Hoisington, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4190 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	274'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 270'. Set bridge plug @ 270' with 35 sx. cement. Filled hole with mud to 35'. Set plug @ 35' and cemented to surface with 15 sx.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jayhawk Drilling Co., Inc.
Address Box 2240, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
H. L. Peel (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. L. Peel

Box 2240, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of March, 19 56.

My commission expires August 13, 1957

Allen P. Denton
RECEIVED
STATE CORPORATION COMMISSION

Notary Public.

24-7368-S 3-53-20M



PLUGGING
FILE SEC 1 T 17 R 21W
BOOK PAGE 45 LINE 31

03-21-1956

15-135-00104-00-00

THE VICKERS PETROLEUM CO., INC.

Irvin #1
NW NW SW Sec. 1-17S-21W
Ness County, Kansas

Casing Record:
10 3/4" @ 274' with 200 sx.

Commenced: February 22, 1956
Completed: March 12, 1956

Elevation: 2179 DF
2181 RB
D & A

LOG

Clay	0-65
Sand	65-75
Shale & shells	75-870
Sand	870-1125
Red beds	1125-1447
Anhydrite	1447-1482
Red beds	1482-1836
Salt	1836-2150
Lime & shale	2150-3060
Shale & lime	3060-3092
Pyrite & shale	3092-3102
Lime & shale	3102-3571
Black shale	3571-3574
Lime	3574-3580
Shale	3580-3594
Lime	3594-3607
Shale	3607-3616
Lime	3616-3906
Shale	3906-3921
Red beds	3921-3962
Cherty lime	3962-4037
Shale & sandy shale	4037-4051
Lime	4051-4063
Shale & sand	4063-4079
Sand	4079-4084
Shale & sand	4084-4109
Chert	4109-4139
Shale & slightly sandy shale	4139-4150
Dolomite	4150-4172
Shale & dolomite	4172-4183
Dolomite	4183-4190

DST #1 4059-4105, op 3/4 H with strong blow decreasing to weak blow near end of test, recovered 2460' SW, FP 165-1052#, SIP 1205#/15 min.

Rotary TD 4190.
Schlumberger TD 4189.

Rotary Bushing Tops:

Heeb	3571
Tor	3594
Lans	3616
Cher sh	4037
Viola dol	4150

03-21-1954

I hereby certify that this Log is true and correct to the best of my knowledge and belief.


THE VICKERS PETROLEUM CO., INC.

BY Ryle Thomas

Subscribed and sworn to before me this 10 day of March, 1956.

Allen J. Denton
Notary Public

My Commission expires August 13, 1957.



PLUGGING
WELL SEC 1 T 17 R 21W
BOOK PAGE 45 LINE 31