


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-00948-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County, Sec. 32 Twp. 13 Rge. 16W (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines NW NE NE
Lease Owner The Carl Todd Drilling Company
Lease Name Dinkel "C" Well No. 1
Office Address 706 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-24 19 56
Application for plugging filed 9-24 19 56
Application for plugging approved 9-24 19 56
Plugging commenced 9-24 19 56
Plugging completed 9-24 19 56
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3517 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
LOG ATTACHED						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 190', set plug and cemented through drill pipe with 15 sacks. Filled hole to 35' set plug and cemented to base of cellar with 10 sacks.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor company tools
Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Carl Todd (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl Todd
706 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of October, 19 56

My commission expires December 14, 1957

Martha Boyz
Notary Public.



PLUGGING
FILE SEC. 32 T. 13 R. 16W
BOOK PAGE 103 LINE 13



RECEIVED
STATE CORPORATION COMMISSION
OCT 5 X 1956
CONSERVATION DIVISION
Wichita, Kansas

THE CARL TODD DRILLING COMPANY
706 Union Center
Wichita, Kansas

#1 Dinkel "C"
NW NE NE Sec. 32-13-16W
Ellis County, Kansas

15051-00948-00-00

COMMENCED: September 14, 1956
COMPLETED: September 24, 1956

ELEVATION: 1959 Rotary Bushing

0 - 20	Surface clay
20 - 200	Clay, shale
200 - 470	Shale
470 - 510	Sand, Pyrite
510 - 515	Sand, shale
515 - 535	Sand, Pyrite
535 - 720	Shale, sand
720 - 830	Shale, shells, Red Bed
830 - 1077	Shale, shells, Red Bed
1077 - 1115	Anhydrite
1115 - 1500	Shale, shells, Red Bed
1500 - 1765	Shale, salt
1765 - 1800	Shale, shells
1800 - 2060	Lime, shale
2060 - 2255	Lime, shale
2255 - 2300	Shale, lime, sandy
2300 - 2415	Lime, shale
2415 - 2620	Lime, shale
2620 - 2690	Shale
2690 - 2855	Shale, lime
2855 - 3110	Lime, shale
3110 - 3241	Lime
3241 - 3327	Lime
3327 - 3469	Lime
3469 - 3517	Cong. and Arb.
3517	Rotary Total Depth

CASING RECORD

8-5/8" casing set at 200' cemented
with 150 sacks

TOPS

Heebner	3168
Toronto	3188
Lansing	3216
Base K. C.	3449
Conglomerate	3466
Arbuckle	3516 ?

DST #1, 3205 - 22, open 1 hour,
recovered 70' slightly oil and gas
cut mud, -BHP 840/30 min.

DST #2, 3231 - 48, open 45",
recovered 6' mud, BHP 0/15 min.

DST #3, 3290 - 3327, open 1 hour,
recovered 60' gas, 120' heavy gas
cut mud, 90' very heavy oil cut mud,
BHP 890/20 min.

I hereby certify that the above is a true and correct log, to
the best of my knowledge and belief.

THE CARL TODD DRILLING COMPANY.

By: *Carl Todd*

PLUGGING
FILE SEC. 32 T. 13 R. 16W
BOOK PAGE 103 LINE 13

RECEIVED
REGISTRATION COMMISSION

OCT 5 X 1956

REGISTRATION DIVISION
Wichita, Kansas