

15.051-19/57.00.00
WELL PLUGGING RECORD

NORTH

Ellis County. Sec. 32 Twp. 13 Rge. 16 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SW SW SW

Lease Owner Cooperative Refinery Association

Lease Name Kuhn "C" Well No. 1

Office Address 911 Central Building

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 15 19 54

Application for plugging filed 11-12 19 54

Application for plugging approved 11-15 19 54

Plugging commenced 11-15 19 54

Plugging completed 11-15 19 54

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 300' feet to 40' feet for each plug set.

R. T. D. 3513' Hole filled with heavy mud up to 300', first plug set @ 300' cemented with 20 sacks cement through drill pipe, hole full of heavy mud from 300' to 40'. Second plug set @ 40' cemented with 10 sacks of cement to surface. Dry & abandoned.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor..... Company Rig #5..... Cooperative Refinery Association
Address..... Box 765..... Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

.....P. H. Jackson.....(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God. *P. H. Jackson*

(Signature)

Box 765 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17 day of November, 1954.

My commission expires August 17, 1957

23-8390-s

6-51-20M

PLUGGING
FILE SEC 321 13 16W
BOOK PAGE 78 LINE 42

Notary Public.

DRILLERS LOG

Kuhn "C" #1

Loc: SW SW SW
 Sec: 32-13-16W
 Ellis County, Kansas
 Operator: Cooperative Refinery Ass'n.
 Contractor: Company Rig #5

Casing 8 5/8" @ 1084' w/525 Saz Common
 & 2% C. C.

Comm: 11-4-54 Comp: 11-16-54
 R. T. D. 3513'

15.051-1915.7.00.00

From	To	Formation
0	275	Surface
275	510	Sand & Shale
510	525	Pyrite Shale Sand
525	640	Shale & Shells
640	760	Dakota Sand
760	840	Shale
840	1080	Red Bed
1080	1090	Andydrite
1090	1510	Lime & Shale
1510	1815	Shale & Shells
1815	1940	Shale & Lime
1940	2050	Lime
2050	3075	Lime & Shale
3075	3415	Lime
3415	3472	Lime & Shale
3472	3513	Lime
3513		R. T. D.

(STATE OF KANSAS)
 (COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the log on the
 Kuhn "C" #1 well, located SW SW SW of section 32-13-16W, Ellis County, Kansas

P. H. Jackson

Subscribed and sworn to before me this 19th day of November, 1954.

Donald E. Hart

My commission expires August 17, 1957.

