



15-051-22875-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION (Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Larry Langhofer of Big Three Drilling, Inc has this date requested permission to plug the following described well:

Operator's Full Name: Energy Three, Inc.

Complete Address: Box 52, Gorham Ks. 67640

Lease Name: E. Dinkel Well No. #1

Location: C of NW SW Sec. 32 Twp. 13 Rge. 16 (E) (W)

County: Ellis Total Depth: 3460'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Larry Langhofer was instructed to plug the well as follows:

8 5/8"-264' s.p. cuc. w/160 sacks common-2% Gel.-3% Cal. Cl.

Ordered 135 sacks of 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 260' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/^{ten}sacks cement

Circulate with 10 sacks of cement in rat hole and 5 sacks in mouse hole.

Very truly yours,


Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1982
CONSERVATION DIVISION
Wichita, Kansas