



15-051-22874-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 22 1982  
CONSERVATION DIVISION  
Wichita Kansas

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Larry Langhofer of Big Three Drilling Inc. has this  
date requested permission to plug the following described well:

Operator's Full Name: Energy Three, Inc.

Complete Address: P.O. Box 1505, Great Bend, Ks. 67530

Lease Name: E. Dinkel Well No. 3572 #1

Location: 80' N. & 60'E. of SW SW Sec. 32 Twp. 13 Rge. 16 (E) (W)

County: Ellis Total Depth: 3500'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A XXX

Other well as hereafter indicated: \_\_\_\_\_

Mr. Langhofer was instructed to plug the well as follows:

8 5/8"-263' S.P. cuc. w/165 sacks common-2% Gel.-3% Cal.Cl.

Ordered 135 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug.

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 250' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement.

Circulate 10 sacks in rat hole & 5 sacks in mouse hole.

Very truly yours,

Conservation Division Agent