



15-051-20797-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. - 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 10 1972
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Hefner of Natl. Oil has this

date requested permission to plug the following described well:

Mr. Hefner guarantees payment of the plugging fee.

Operator's full Name: National Oil Co.

Complete Address: 200 W. Douglas Wichita, Ks.

Lease Name: Dinkel Well No. 1

Location: NE SW NE Sec. 32 Twp. 13 Rge. (E)(W) 16

County: Ellis Total Depth 3472' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Hefner was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and displace
70 sk cmt thru drill pipe. Heavy mud to 180' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Messing
 Conservation Division Agent