



15-135-20791-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 17 1973  
09-17-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Norwood of DNE Drlg. has this  
date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: DNE Drlg., Inc.

Complete Address: 701 First National Bank Bldg., Wichita, Ks.

Lease Name: Stieber Well No. I

Location: C SW SE Sec. 19 Twp. 17 Rge. (E)(W) 21

County: Ness Total Depth 4330' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Norwood was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 500' and displace  
50 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and  
displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Mussey  
Conservation Division Agent