

State of Kansas



15-135-20015-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 3 1967
03-03-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Burton of Pickrell Drilling Co. has this

date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg. Wichita, Kansas

Lease Name: Elmore "D" Well No. 3

Location: C E/2 SW NE Sec. 14 Twp. 17 Rge. 21 (E)(W) X

County Ness Total Depth 4160 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace

25 sc cement thru drill pipe. Heavy mud to 390' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole with

2 sc cement.

Very truly yours,

Leo J. Massey
Conservation Division Agent