

15-135-20178-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ness County, Sec. 23 Twp. 17 Rge. 21 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines CSW NW
Lease Owner Pickrell Drilling Co.
Lease Name Ryan Estate Well No. 1
Office Address 705 Fourth Natl. Bank Bldg. Wichita
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed Sept. 14, 19 68
Application for plugging filed Sept. 30, 19 68
Application for plugging approved Sept. 30, 19 68
Plugging commenced Sept. 30, 19 68
Plugging completed Oct. 25, 19 68
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4211 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 248' | None |
| | | | | 5 1/2 | 4207' | 3244' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand from 4181' to 4080'. Mixed and dumped 5 sx. of cement from 4080' to 4040'. Pulled casing. Mixed and pumped in 20 sx. of gel and 5 sx. of hulls. Mixed and pumped in 110 sx. of pozmix plus 6% gel from 567' to base of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1968
CONSERVATION DIVISION
Wichita, Kansas

10-31-1968

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Russ Casing Pulling Inc.
Address Box 1082 Great Bend, Ks.


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Bill J. Porter (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill J. Porter

705 4th Nat'l Bank Bldg, Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of October, 19 68



My commission expires May 10, 1970 L. M. Whiting Notary Public.

15-135-20178-00-00

ROTARY DRILLING LOG

Copy Mailed
WLB 9-9-68

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bank Bldg.
Wichita, Kansas
LOCATION: Ryan Estate No. 1, C SW NW Sec. 23-17S-21W
Ness County, Kansas
CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

Rotary Drilling Commenced 8-22-68
Rotary Drilling Completed 8-31-68

CASING RECORD: Ran 6 jts. used 20# 8 5/8" casing 248' KB. 160 Sacks cement.
Circulated 2 P.M. Spud 10:15
Ran 130 jts. 5 1/2" oo 14# Casing 4200.28'. Set 4' off bottom
at 4207' KB. Cemented with 125 sacks Salt Saturated Common Cement.
Circ. good. Plugged down at 5:45 PM 8/31/68.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

| | | |
|------|---------------------|--------------------|
| 50 | Surface Soil & Clay | <u>C. F. S.</u> |
| 248 | Shale & Shells | |
| 248 | Cement | 4102 |
| 725 | Shale | 4106 |
| 890 | Red Bed & Shale | 4116 |
| 1456 | Shale & Sand Stks | 4130 |
| 1493 | Anhydrite | 4140 |
| 2150 | Shale | 4150 |
| 2450 | Shale & Lime | 4170 |
| 2535 | Lime | 4180 |
| 3965 | Lime | |
| 4107 | Shale & Lime | |
| 4116 | Shale & Sand | |
| 4140 | Lime, Shale & Sand | <u>Slope Tests</u> |
| 4210 | Mississippian TD | |
| | | 2500 |
| | | 3000 |
| | | 3500 |
| | | 4000 |
| | | <u>S. L. M.</u> |
| | | 4107.68 |
| | | 4107.15 |
| | | <u>.53</u> |

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1968
CONSERVATION DIVISION
Wichita, Kansas

09-30-1968

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On _____ day of August, 1968, before me the undersigned, a Notary Public, in and for the State of Kansas, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and lawful act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.
My commission expires: May 10, 1970

[Signature]
L. M. Whiting Notary Public