


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-135-00006-00-00
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ness County, Sec. 21 Twp. 17S Rge. (E) 21 (W)
Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Sunray Mid-Continent Oil Company
Lease Name J. P. Moran Well No. 1
Office Address Box 788, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 20 19 60
Application for plugging filed 19
Application for plugging approved April 20 19 60
Plugging commenced April 20 19 60
Plugging completed April 20 19 60
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert P. Leiker
Producing formation Depth to top Bottom Total Depth of Well 4310 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8" OD	382	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Wooden Plug at 600' with 20 sacks cement on top of plug from 535' to 600'
Wooden Plug at 380' with 20 sacks cement on top of plug from 315' to 380'
Wooden plug at 40' with one-half sack hulls and 10 sacks cement from 40' to surface.

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1960
CONSERVATION DIVISION
Wichita, Kansas
05-06-1960

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Stickle Drilling Company
Address Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.
James R. Nichols (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
P. O. Box 788, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5 th. day of May, 19 60

My commission expires December 24, 1960 Notary Public.



Sunray Mid-Continent Oil Company
Tulsa, Oklahoma

15-135-00006-00-00

Tulsa, Oklahoma
April 22, 1960

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: April 7, 1960
Drilling Completed: April 20, 1960

J. P. Moran #1 NE NE SW
Section 21-17S-21W., Ness
County, Kansas.

DRILLERS LOG

Depth Figures Indicate Base Of Formation:

Surface	0
Clay Sand & Shale	180
Shale & Sand Streaks	384
Sand	435
Shale & Sand Streaks	730
Shale & Red Bed	915
Sand	1190
Shale & Red Bed	1497
Anhydrite	1532
Shale & Shells	2215
Lime & Shale	3805
Lime	3887
Lime & Shale	4055
Lime (Cherty) Shale	4083
Lime & Chert	4120
Lime & Shale	4160
Shale, Lime & Sand	4200
Shale & Lime	4228
Shale, Lime, Chert	4265
Lime & Chert	4310 TD

STATE GEOLOGICAL SURVEY OF KANSAS
MAY 6 1960
CONSERVATION DIVISION
Wichita, Kansas
05-06-1960

I, Fred E. Stickle, hereby certify the above to be a true and complete
Drillers Log of Sunray Mid-Continent Oil Company's J. P. Moran #1 NE NE
SW Section 21-17S-21W., Ness County, Kansas.


Fred E. Stickle


Notary Public

January 8 1964
My Commission Expires