

15-135-23288-00-01


STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ness SEC. 20 TWP. 17S RGE. 21W E/W
Location as in quarters or footage from lines:
1320' North from SE Corner, 2970' West from SE Corner



Locate Well
correctly on above
Section Platt.

Lease Owner ZPC Petroleum, Inc.
Lease Name Brenner Well No. 1-20
Office Address 9319 E. Harry #122
Character of Well (Completed as Oil, Gas or Dry Hole): D&A
Date Well Completed July 1, 1989
Application for plugging filed August 2, 1989
Plugging commenced August 25, 1989
Plugging completed August 25, 1989
Reason for abandonment of well or producing formation production

non-commercial
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dan Goodrow
Producing formation Mississippi Dolo. Depth to top 4292' bottom 4302' T.D. 4339'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Mississippian Dolomite	10° Grav. Oil	4292'	4294'	4 1/2"	4339'	none
Lansing 'K'	water	3964'	3970'			
Lansing 'J'	water	3939'	3941'			
Lansing 'I'	water	3908'	3910'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. August 25, 1989 10:00A.M. - Haliburton on location to plug well. Mixed 30 sx of econolite cement w/300# of hulls. Pumped rubber plug to 3000'. Pressure increased to 650#, holding @ 400#. Release pressure. Perforate @ 800' w/ 2 shots. Mixed 100 sx 60/40 pozmix (6% gel) w/ 100# of hulls. Fluid circulating out backside. Very good mud. Pressure to 650#, holding @ 400#. Hook up to backside and mix 100 sx 60/40 pozmix (6% gel). Pressure up to 800#, shut-in @ 400#.

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1989

09-13-1989
Wichita Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Haliburton Services

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Jon R. Stewart (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Jon R. Stewart
9319 E. HARRY #122
WICHITA, KS. 67207 (Address)

My Commission expires: 1/18/93
AND SWORN TO before me this 11th day of September, 1989
Richard W. Ediger Notary Public.

