

15-135-20135-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 20 Twp. 17S Rge. (E) 21 (W)

Location as "NE/CNWKSWK" or footage from lines. C NW NE  
Lease Owner Rains & Williamson Oil Co., Inc.  
Lease Name BRENNER "B" Well No. 1  
Office Address 1425 Wichita Plaza - Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 3-29 19 68  
Application for plugging filed 4-7 19 68  
Application for plugging approved 4-7 19 68  
Plugging commenced 4-7 19 68  
Plugging completed 1:45 PM 4-7 19 68  
Reason for abandonment of well or producing formation No oil or gas found  
in commercial quantities.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Bill Nichols (for Leo Massey) Morland, Kansas  
Producing formation None Depth to top Bottom Total Depth of Well 4300 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	537'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug to 750' and spotted 75 sacks 50-50 Pozmix, 1% gel.  
Mudded back to 40'. Set solid bridge and capped with 10 sacks,  
2 sacks in rat hole. Plugging completed at 1:45 PM, 4-7-68.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 10 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
04-10-1968

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.  
Address 1425 Wichita Plaza - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Wilson Rains (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains  
1425 Wichita Plaza - Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 9th day of April 19 68  
June 30, 1971 Sherry Gish Notary Public.



15-135-20135-00-00

ROTARY DRILLING LOG

Operator: Rains & Williamson Oil Co., Inc.  
BRENNER "B" #1  
C NW NE Section 20-17S-21W  
Ness County, Kansas

Contractor: Rains & Williamson  
Oil Co., Inc.  
Commenced: 3-29-68  
Completed: 4-7-68

Remarks: Set 8-5/8" surface casing at 537' w/ 300 sacks GL-3 cement.

Formations:

Soil and Clay	40'
Shale	539'
Shale and Red Bed	940'
Sand	1205'
Shale and Red Bed	1522'
Anhydrite	1571'
Shale	1595'
Shale and Shells	2140'
Shale	2220'
Lime and Shale	2600'
Lime	2710'
Lime and Shale	3220'
Shale and Lime	3330'
Lime and Shale	3775'
Lime	4204'
Lime and Sand	4240'
Lime	4300'
Rotary Total Depth (D & A)	4300'

04-10-1968  
RECEIVED  
STATE CORPORATION COMMISSION  
APR 10 1968  
CONSERVATION DIVISION  
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.

*Wilson Rains*  
Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the State of Kansas, County of Sedgwick, this 9th day of April, 1968.

*Sherry Gish*  
Sherry Gish Notary Public

My Commission Expires: June 30, 1971

