


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 27 Twp. 17S Rge. (E) 21 (W)
Location as "NE/CNW/SSW" or footage from lines C NW NE
Lease Owner Pickrell Drilling Company
Lease Name Travis No. 1 Well No.
Office Address 705 4th National Bank Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 25, 19 65
Application for plugging filed January 25, 19 65
Application for plugging approved January 25, 19 65
Plugging commenced January 25, 19 65
Plugging completed January 25, 19 65
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4275 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 266' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rec'd

Heavy mud to 600', set plug, cemented with 25 sacks cement. Heavy mud to 240', set plug, cemented with 20 sacks cement. Heavy mud to 40', set plug, cemented with 10 sacks cement to bottom of cellar. Plugged rat hole with 2 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Building, Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Pickrell Drilling Company (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebits
705 4th National Bank Bldg, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of February, 19 65

My commission expires June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public.



ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th Ntl Bank Bldg
Wichita, Kansas

Rotary Drilling Commenced 1-15-65

Rotary Drilling Completed 1-24-65

LOCATION: Travis No. 1, C NW NE Section 27-17-21W, Ness County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (13 jts) 8 5/8" surface casing set at 266' cemented with 155 sacks cement. Circulated. Completed 3:45 P.M. January 15, 1965. No oil string run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

| | | |
|------|---------------------|--------------------|
| 160 | Lime & Clay | <u>C. F. S.</u> |
| 266 | Blue Shale & Shells | 4142 |
| 905 | Shale & Shells | 4160 |
| 1115 | Sand | 4175 |
| 1215 | Shale | 4200 |
| 1445 | Red Beds, Shale | 4190 |
| 1485 | Anhydrite | 4205 |
| 1895 | Shale & Shells | 4220 |
| 2225 | Shale | 4227 |
| 2425 | Lime & Shale | 4240 |
| 2725 | Lime | 4275 |
| 3565 | Lime & Shale | |
| 3618 | Sandy Lime & Shale | |
| 3665 | Lime & Shale | <u>Slope Tests</u> |
| 3705 | Lime | 2500 |
| 3765 | Lime & Shale | 3000 |
| 3938 | Lime | 3550 |
| 4140 | Lime & Shale | 4025 |
| 4175 | Cherokee | |
| 4235 | Shale & Lime | <u>S. L. M.</u> |
| 4270 | Mississippian Chert | 3505 |
| 4275 | Mississippian - RTD | 3825 |
| | | 4111 |

RECEIVED
STATE CORPORATION COMMISSION

FEB 10 1965
02-10-1965
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts
C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 1st day of February, 19 65, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public

