

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

Form CP-4  
 Rev. 12-15-80

WELL PLUGGING RECORD 15-135-22273-00-00

Give All Information Completely  
 Make Required Affidavit

COUNTY Ness SEC. 21 TWP. 17 RGE. 21W E/W  
 Location as in quarters or footage from lines:  
 NE SW SE


Lease Owner Hummon Corporation  
 Lease Name Bill McCormic #1 Well No. \_\_\_\_\_  
 Office Address 400 One Main Place Wichita, Ks. 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 10-9-82  
 Plugging completed 10-13-82  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
 correctly on above  
 Section Platt.

\_\_\_\_\_ Depleted  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4225'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	434'	none
				4-1/2"	4221'	3525'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

~~Plugged off bottom with sand to 4175' and ran 4 sacks cement. Shot casing @3605', 3520' and pulled a total of 100 joints of 4-1/2". Plugged well with 3 sacks hulls, 20 sacks gel, 60 sacks cement, 1 sack hulls, 20 sacks gel, released plug and displaced with 115 sacks cement.~~

~~Plugging Complete.~~

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
 Box 347 Chase, Ks. 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of October, 19 82

My Commission expires: \_\_\_\_\_



Irene Hoover  
 Notary Public.

RECEIVED  
 STATE CORPORATION COMMISSION

OCT 19 1982  
 10-19-1982  
 CONSERVATION DIVISION  
 Wichita, Kansas

DRILLERS LOG

15-135-22273-00-00

#1 Bill McCormick

CASING RECORD:

8-5/8" @ 434'  
w/ 300 sx. cement  
4-1/2" @ 4221'  
w/ 125 sx. cement

COMPANY: Hummon Corporation

CONTRACTOR: Big-H Drilling, Inc.

COMMENCED: July 26, 1982

COMPLETED: August 6, 1982

DESCRIPTION:

NE SW SE  
Sec. 27-17S-21W  
Ness County, KS  
RTD: 4225'

FORMATION

FROM

TO

REMARKS

Clay & Shale	0	440	
Red Beds & Shale	440	1255	
Shale	1255	1765	
Lime & Shale	1765	1836	
Shale & Lime	1836	2772	
Lime & Shale	2772	3212	
Shale & Lime	3212	3412	
Lime & Shale	3412	4128	
Lime & Sand	4128	4165	
Lime & Shale	4165	4219	
Lime & Chert & Shale	4219	4225	
RTD		4225	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

BIG-H DRILLING, INC.

*Karen R. Tennis*  
\_\_\_\_\_  
Karen R. Tennis

Subscribed and sworn to before me this 12th day of August, 1982.

SANDRA L. MENDOZA  
STATE NOTARY PUBLIC  
SEDGWICK COUNTY, KANSAS  
MY APPT. EXP. 2/19/86

RECEIVED  
STATE CORPORATIONS COMMISSION  
*Sandra L. Mendoza*  
Public  
SEP 15 1982  
CONFIRMATION  
09-15-1982