


15-135-20435-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

NESS County, Sec. 25 Twp. 17 Rge. 21W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW NW
Lease Owner Chief Drilling Co., Inc.
Lease Name Irvin Well No. #1
Office Address Suite 905 Century Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed April 28, 1971 19
Application for plugging filed April 28, 1971 19
Application for plugging approved April 28, 1971 19
Plugging commenced April 28, 1971 19
Plugging completed April 28, 1971 at 3:30 P.M. 19
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4195' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	447'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


Plugged through drill pipe @ 550' w/50 sacks cement
Plugged through drill pipe @ 240' w/25 sacks cement
Plugged through drill pipe @ 40' w/10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1971
CONSERVATION DIVISION
Wichita, Kansas
04-30-1971

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address Suite 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jim Robinson (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
Suite 905 Century Plaza, Wichita, Kansas
(Address)



Subscribed and Sworn to before me this 29th day of April, 19 71
Karen E. Duarte
Karen E. Duarte Notary Public.

February 16, 1974

15-135-20435-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 1971
CONSERVATION DIVISION
Wichita, Kansas

05-03-1971
#1 IRVIN
C NW NW Sec. 25-17-21W
Ness County, Kansas

WELL LOG

Chief Drilling Co., Inc.
Suite 905 Century Plaza
Wichita, Kansas 67202

CONTRACTOR: Company tools
CASING RECORD: Set 8 5/8" @ 447' w/235 sacks
Common Quickset

Commenced: 4/19/71
Completed: 4/28/71 (D & A)

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface sand & clay	0	100	2177-Gr.
Sand & shale	100	447	2179 D.F.
Shale	447	500	2182 K.B.
Shale & sand	500	1431	
Anhydrite	1431	1461	<u>FORMATION TOPS</u>
Shale & shells	1461	2245	Anhydrite 1431 + 751
Shale & lime	2245	3580	Base Anhydrite 1461 + 721
Lime	3580	4035	Heebner 3582 -1400
Lime & shale	4035	4099	Toronto 3600 -1418
Cherokee	4099	4104	Lansing 3622 -1440
Lime	4104	4160	Base K.C. 3920 -1738
Cherty lime & shale	4160	4195	Pawnee 3997 -1815
Total Depth	4195		Ft. Scott 4071 -1889
			First Sand 4091 -1901
			Shaley Miss. 4162 -1980
			Total Depth 4195 -2013
			No Log Run

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C NW NW of Section 25-17-21W, Ness County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
Jim Robinson, Office Manager

Subscribed and sworn to before me this 30th day of April, 1971.

Karen E. Duarte
Karen E. Duarte, Notary Public

