

LEASE NAME Janke

WELL NUMBER # 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

460' Ft. from S Section Line

3300' Ft. from E Section Line

SEC. 34 TWP. 17s RGE 21w (N) or (W)

COUNTY Ness

LEASE OPERATOR Castle Resources Inc.

ADDRESS 1200 E. 27th Hays., Kansas 67601

PHONE# (913) 625-5155 OPERATORS LICENSE NO. 9860

Date Well Completed 9/2/82

Character of Well oil

Plugging Commenced 2/6/97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2/6/97

The plugging proposal was approved on 1/25/97 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Ft. Scott Depth to Top 4097' Bottom 4100' T.D. 4272'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface Pipe	0	399'	85/8"	399'	None
	Prod. casing	0	4272'	41/2"	4272'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Mix 200# of hulls and 20 sks. of 60-40 pos. 6% gel. Pump to perfs. Pressure to 1200#. Release pressure. ELI. perf. @ 700'. Allied Cementing mix 200 sks. of 60-40 pos. 6% gel. Circulating to pit. Circulate 10 sks. to pit.
Ticket# 1567

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address P.O. Box 31 Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Castle Resources, Inc.

STATE OF KANSAS COUNTY OF Ellis, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dean Dues


(Address) 1209 Haney, Co.

SUBSCRIBED AND SWORN TO before me this 21st day of February, 1997

Gloria A. Rader

Notary Public

My Commission Expires:



02-24-1997
RECEIVED
KANSAS CORP COM
1997 FEB 24 P 3