

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-22,181000

LEASE NAME McCormick

WELL NUMBER #34-14

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

660 Ft. from S Section Line

3,300 Ft. from E Section Line

SEC. 34 TWP. 17 RGE 21 (S or (W))

LEASE OPERATOR Apollo Energies

COUNTY Ness

ADDRESS 520 Ridgeway Pratt, Ks 67124

PHONE# (316) 672-7324 OPERATORS LICENSE NO. 9732

Date Well Completed 2-16-82

Character of Well _____

Plugging Commenced 12-7-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-7-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Ft. Scott Depth to Top 4106 Bottom 4110 T.D. 4325

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Ft. Scott</u>	<u>Oil</u>	<u>4106</u>	<u>4110</u>	<u>5 1/2"</u>	<u>1-12-82</u>	<u>12-7-85</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Ft. Scott Sanded in by Cedar Hills Csg. Leak to 4070'. Cont'd. Run TBG below 1200' due to bridge Pumped 75x Cement at 1188' - 5 1/2" Csg. eaten into at 832' KB. Pulled 832' 5 1/2" Csg. Halliburton pumped down surface 3 hls, 15 gal, 50sx 60-40 Poz-mix 10gal, 1 hls. Plug, + 200 Sx Poz-mix 6% gel on top (If additional description is necessary, use BACK of this form.) S.I. e 300 PSI.

Name of Plugging Contractor Hembeck Well Service, Inc. License No. 6907

Address P.O. Box 458 Ness City Ks 67560

STATE OF KANSAS COUNTY OF PRATT, ss.

JAMES L. BYRNS - Operator (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James L. Byrns
(Address) 520 Ridgeway - Pratt, Ks 67124

SUBSCRIBED AND SWORN TO before me this 12th day of February, 19 86

BARBARA J. SVOBODA
NOTARY PUBLIC
STATE OF KANSAS
My Commission Expires: 12-16-89

Barbara J. Svoboda
Notary Public
RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1986
02-13-1986
CONSERVATION DIVISION
Wichita, Kansas