

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-135-23,396-00-00

LEASE NAME Mishler

WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

330 Ft. from S Section Line

4,290 Ft. from E Section Line

SEC. 15 TWP. 17 RGE. 25 ~~W~~ or (W)

COUNTY Ness

Date Well Completed 11-8-89

Plugging Commenced 11-8-89

Plugging Completed 11-8-89

LEASE OPERATOR Shields Oil Producers, Inc.

ADDRESS Shields Bldg., Russell, Kansas 67665

PHONE#(913) 483-3141 OPERATORS LICENSE NO. 5184

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-8-89 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4,482'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	259'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Fill hole w/heavy mud. Push bridge plug to 1,830', spot 50 sax cement on plug thru drill pipe. Push bridge plug to 1,000', spot 80 sax cement on plug thru drill pipe. Push bridge plug to 290', spot 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co., Inc. License No. 164 RECEIVED

Address Shields Bldg., Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, Inc. NOV 30 1989

STATE OF KANSAS COUNTY OF RUSSELL, ss. CONSERVATION DIVISION
 Wichita, Kansas

Jack P. Beeman (Employee of Operator) or ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec - Treas

(Address) Shields Bldg., Russell, Ks. 67665

SUBSCRIBED AND SWORN TO before me this 28th day of November, 19 89

Ruth Phillips
 Notary Public
 My Commission Expires: 3-26-91

My Commission Expires: _____