


15-BS-20850-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

C/NE SW County, Sec. 7 Twp. 17S Rge. (E) 25(W)  
Location as "NE/CNW/SW" or footage from lines C/NE SW  
Lease Owner Thunderbird Drilling, Inc.  
Lease Name Stutz "T" Well No. 1  
Office Address Box 18107, 4328 East Kellogg, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole 67218  
Date well completed March 3 19 74  
Application for plugging filed March 3 19 74  
Application for plugging approved March 3 19 74  
Plugging commenced March 3 19 74  
Plugging completed March 3 19 74  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4534 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	330'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged as follows: Plugged at 750' with 70 sacks of 50-50 pozmix & 6% gel; plugged at 270' with 20 sacks of 50-50 pozmix & 6% gel; plugged at 40' with 10 sacks of 50-50 pozmix & 6% gel. Plug down at 7:30 P. M. March 3, 1974.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 8 1974  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Strata Drilling Company  
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Kenneth J. Link (as lessee or owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link  
Kenneth J. Link  
P. O. Box 355, Great Bend, Kansas 67530  
(Address)

Subscribed and sworn to before me this 6th day of March, 1974.  
December 14, 1977  
Elaine H. Taylor  
Notary Public.



15-135-20850-00-00

D R I L L E R S   L O G

#1 Stutz "T"

CASING RECORD:  
330' of used 8-5/8"  
surface casing.

COMPANY: Thunderbird Drilling, Inc.

DESCRIPTION:  
C/NE SW  
Sec. 7-17S-25W

CONTRACTOR: Strata Drilling Company

TOTAL DEPTH:  
4534'

COMMENCED: February 22, 1974

COMPLETED: March 3, 1974

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay	0	130	Ran 325' of used 8-5/8" surface casing; set and cemented at 330' with 200 sacks of common cement, 2% gel and 3% C. C. Plug down at 8:15 P. M. February 22, 1974.
Shale & Hard Sand	130	350	
Shale	350	1100	
Shale & Sand	1100	1680	
Shale	1680	1885	
Anhydrite	1885	1930	
Shale & Lime	1930	3074	
Lime, Shale & Chalk	3074	3162	
Shale & Lime	3162	3325	
Lime & Shale	3325	4425	
Lime	4425	4495	
Lime & Shale	4495	4534	

ROTARY TOTAL DEPTH: 4534'

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 8 1974  
CONSERVATION DIVISION  
Wichita, Kansas

D. & A.

Hole plugged as follows:  
Plugged at 750' with 70 sacks of 50-50 pozmix & 6% gel;  
plugged at 270' with 20 sacks of 50-50 pozmix & 6% gel;  
plugged at 40' with 10 sacks of 50-50 pozmix & 6% gel.  
Plug down at 7:30 P. M. March 3, 1974.

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

*Kenneth J. Link*  
Kenneth J. Link

Subscribed and sworn to before me this 6th day of March, 1974.

My Commission Expires:

December 14, 1977

*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public