

KCC OIL/GAS REGULATORY OFFICES

Date: 01/20/12

District: 1

Case #: _____

- New Situation
- Response to Request
- Follow-Up

- Lease Inspection
- Complaint
- Field Report

Operator License No: 34318

API Well Number: 15-083-21742-00-00

Op Name: Berexco, L.L.C.

Spot: SE-SW-NE-SW Sec 17 Twp 22 S Rng 22 E / W

Address 1: 2020 N. Bramblewood

1570 Feet from N / S Line of Section

Address 2: _____

1847 Feet from E / W Line of Section

City: Wichita

GPS: Lat: 38.13532 Long: 99.76470 Date: 1/20/12

State: KS Zip Code: 67206 -1094

Lease Name: Douglas Well #: 1X

Operator Phone #: (316) 265-3311

County: Hodgeman

Reason for Investigation:

Company requested a state witness to finish the alternate II cementing job.

Problem:

Alternate II cementing requirements have not been met.

Persons Contacted:

Mark Leiker.

Findings:

8 5/8" was set @ 250'. 5 1/2" was set @ 4543' with 300 sx cement. DV tool @ 2606'. Consolidated pumped 375 sx cement through the DV tool, but cement did not circulate. Perf-Tech ran a cement bond log and found top of cement at app. 690'. Perforated @ 690'. Quality Well Service pumped 270 sx cement, circulating 25 sx to the pit.

Action/Recommendations:

Follow Up Required Yes No

Date: _____

None. Alternate II cementing requirements have been met.

60/40 poz, 4% gel, 1/4# polyflake by Quality Well Service.

Verification Sources:

Photos Taken: 0

- RBDMS
- T-I Database
- Other: On-site witness
- KGS
- District Files
- TA Program
- Courthouse

By: Eric MacLaren
Eric MacLaren

Retain 1 Copy District Office
Send 1 Copy to Conservation Division

RECEIVED

FEB 08 2012

Form: _____

KCC WICHITA