

15-101-21688 ~~5500~~

ALTZ

KCC OIL/GAS REGULATORY OFFICE

DATE 12/12/94

New Situation  
 Response to Request  
 Follow-up

OPERATOR Hellar Drilling Co. Inc. # 5015

NAME 125 N. Market, Ste. 1422

LOCATION SW, SEC 5, T 16 S, R 27 W

& ADDRESS Wichita, KS 67202

LEASE Christian Church Well # 2

PHONE NO. 316-267-2845 OTHER \_\_\_\_\_

COUNTY Lane  
API# 15-101-21,688

REASON FOR INVESTIGATION: The company is completing this well to become a disposal well (Docket #D-27,031).

LEASE INSPECTION

PROBLEM: The operator attempted to circulate cement back to surface from the bottom of the pipe to satisfy the Alternate II requirements. This attempt failed.

PERSON(S) CONTACTED: Ron Schrader

FINDINGS: The well has 257' of 8 5/8" surface pipe. The 5 1/2" casing was set at 1863'. The primary cement job only raised cement to 1125' according to the bond log. Today they perforated the 5 1/2" at 1050-1051'. Allied Cementing established circulation up the 8 5/8" X 5 1/2" annulus with gel mud. Then the well was cemented with 200 sx 60/40 Pozmix 6% gel 3% cc 1/4# Flowcel tailed in with 75 sx common cement 3% cc. The job had good returns, circulating 15 barrels of cement to the pit.

COMPLAINT

ACTION/RECOMMENDATIONS: The well has met its Alternate II requirement and is ready to be completed. Case closed.

photos taken: \_\_\_\_\_

FIELD REPORT

Retain 1 copy Joint District Office  
Send 1 copy Conservation Division

By Richard W. Lacey  
12/12/94

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 14 1994  
REGISTRATION DIVISION  
WICHITA, KANSAS