

15-135-20341-0000

WLOG

DRILLERS LOG

#1 Clyne

CASING RECORD:  
326' of used 8-5/8"  
surface casing.

COMPANY: Okmar Oil Company  
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: C/SE SW  
Section 2-16S-25W  
Ness County, Kansas

TOTAL DEPTH:  
4505'

COMMENCED: May 18, 1970  
COMPLETED: May 26, 1970

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post Rock, Shale, Clay & Sand	0	340	Ran 326' of used 8-5/8" surface casing; set and cemented at 326' with 170 sacks of regular cement, 2% gel and 3% C. C. Plug down at 8:45 P. M. May 18, 1970.
Shale & Clay	340	690	
Shale, Shells w/Sand Streaks	690	925	
Red Bed, Shells & Sand Streaks	925	1335	
#1 Anhydrite	1335	1346	
Red Bed	1346	1414	
Dakota Sand	1414	1688	
Red Bed & Shells	1688	1939	
#2 Anhydrite	1939	1975	
Shale, Sand, Shells & Rock	1975	2317	
Shale & Shells	2317	2609	
Shells, Shale & Lime	2609	2809	
Shale & Lime	2809	4177	
Lime	4177	4260	
Lime w/Broken Lime Streaks	4260	4300	
Lime & Shale	4300	4390	
Lime & Chert	4390	4435	
Lime	4435	4437	
Lime & Shale	4437	4505	

Rotary Total Depth 4505'

Ran 143 joints (4503') of 5 1/2" used casing; set and cemented at 4500' with 125 sacks of common cement, salt saturated. Plug down at 1:30 P. M. May 26, 1970.


STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*Charles W. Steincamp*  
Charles W. Steincamp, President

Subscribed and sworn to before me this 27th day of May, 1970.



*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public

RECEIVED  
STATE OF KANSAS COMMISSION

AUG 09 1991  
CONSERVATION DIVISION  
Wichita, Kansas