

D R I L L E R S    L O G

#2 Kaler

CASING RECORD:  
323.70' of used 8-5/8"  
surface casing.

COMPANY:    Okmar Oil Company  
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: C/SW SE  
Section 2-16S-25W  
Ness County, Kansas

TOTAL DEPTH:  
4490'

COMMENCED: March 8, 1970  
COMPLETED: March 17, 1970

ELEVATION: 2532' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Rock & Shale	0	339	Ran 323.70' of used 8-5/8" surface casing; set and cemented at 323.70' with 170 sacks of regular cement, 2% gel and 3% C. C. Plug down at 4:10 P. M.
Shale	339	1094	
Red Bed, Shells & Sand Streaks	1094	1315	
#1 Anhydrite	1315	1328	
Red Bed & Shells	1328	1392	
Dakota Sand	1392	1668	
Shale & Shells	1668	1918	
#2 Anhydrite	1918	1955	
Red Bed, Shale w/Broken Lime	1955	2220	
Shale w/Broken Lime	2220	2518	
Shale & Lime	2518	2743	
Lime, Shale w/Broken Lime	2743	2946	
Shale & Lime	2946	3948	
Shale & Lime Streaks	3948	3948	
Lime	3948	4115	
Lime & Shale	4115	4220	
Lime	4220	4420	
Lime & Chert	4420	4490	5 1/2" casing set and cemented at 4483' with 125 sacks of cement, salt saturated.
Total Depth 4490'			

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*Charles W. Steincamp*  
Charles W. Steincamp, President

Subscribed and sworn to before me this 17th day of March, 1970.



*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

AUG 09 1991

... DIVISION  
... Kansas

STATE OF KANSAS  
STATE CORPORATION COMMISSION-CONSERVATION DIVISION  
500 Insurance Building-212 North Market  
Wichita 2, Kansas

DATA AND AFFIDAVIT

(File one Copy)

(On Cementing In Surface or Drive Pipe and required by Rule 82-2-123 of the Commission for compliance with Section 55-136, 55-137, and 55-138, 1947 Supplement to G. S. Kansas 1935)

Lease Owner Okmar Oil Company

Office Address 1130 Wichita Plaza, Wichita, Kansas 67202

Lease Name Kaler Well No. 2

Well Location (Example: C N/2 NE/4 NE/4 or footage from lines)  
C/SW SE SEC 2 TWP 16S RGE 25W (E) County Ness

Contractor Strata Drilling, Inc.

Office Address P. O. Box 355, Great Bend, Kansas 67530

Drilled with (cable) (Rotary) tools: Date pipe set 3-9 19 70

SURFACE HOLE DATA

SURFACE PIPE DATA

Size of Hole 12 1/4" Csg. (New) (Used) Size 8-5/8" Wt. 20#

Depth 323.70' Where set 323.70'

METHOD OF CEMENTING

(a) Cement: Amount and kind 170 sacks of regular cement

Method: (By Service Co., Dump, Tog., etc.) Service

Est. Height Cement behind pipe \_\_\_\_\_

(b) Cementing Material: Explain method. (Example: 8-5/8 w/swag nipple run inside 15", Bridge hold 2/rock and hole filled with cementing material, 15" pipe pulled.) Ran 323.70' of used 8-5/8" surface

casing; set and cemented at 323.70' with 170 sacks of regular cement, 2% gel

and 3% C. C. Plug down at 4:10 P. M. March 9, 1970.

Describe cementing material Regular cement, gel and C. C.

GROUND WATER INFORMATION

Depth to bottom of lowest fresh water producing stratum \_\_\_\_\_

Name of lowest fresh water producing stratum \_\_\_\_\_

Surface elevation of well \_\_\_\_\_

ADDITIONAL INFORMATION

RECEIVED  
STATE CORPORATION COMMISSION

AUG 09 1991

CONSERVATION DIVISION  
Wichita, Kansas

(Additional Information may be submitted on separate sheet)

A F F I D A V I T

STATE OF KANSAS, COUNTY OF BARTON SS,

I, Charles W. Steincamp, of the Strata Drilg., Inc. COMPANY, being  
fully and duly sworn on oath, state: That I, have knowledge of the facts,  
and matters herein contained and that the same are true

STRATA DRILLING, INC.

Charles W. Steincamp

Subscribed and sworn to before me on this 17th day of March 1970  
My Commission Expires:

Elaine H. Taylor  
Elaine H. Taylor, Notary Public

