

15-101-20093-00-00

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 13 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling, Incorporated,

Complete Address P. O. Box #18407, Wichita, Kansas.

Lease Name Koehler Well No. 2

Location N/2-NE-NW Sec. 19 Twp. 17 Rge. (E) (W) 27

County Lane Total Depth 4610'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil Company, Incorporated,

Address 435 Page Court, Wichita, Kansas. License No.

Operation Completed: Hour 6:00 PM Day 10 Month 3 Year 1974

The above well was plugged as follows:

361'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 700'.

Circulated hole with heavy mud. Pulled DP to 925' and displaced 110 Cu. Ft. cement
thru DP from 925' to 600'. Pulled DP to 375' and displaced 30 Cu. Ft. cement thru
DP from 375' to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 3/18/74
INV. No. 8761-U