

15-101-20130-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 15 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Mallonee - Mahoney, Incorporated,

Complete Address 925 Sutton Place, Wichita, Kansas.

Lease Name L. Waterson Well No. 1

Location NE-NW-NW Sec. 18 Twp. 17 Rge. (E) (W) 27

County Lane Total Depth 4045'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No.     

Operation Completed: Hour 3:30 PM Day 10 Month 11 Year 1974

The above well was plugged as follows:

342'--8 5/8" Surface casing, cement circulated with 250 Sx.  
Top of Dakota section @ 775'.

Circulated hole with heavy mud. Pulled DP to 1000' and displaced 110 Cu. Ft. cement  
thru DP from 1000' to 675'. Pulled DP to 340' and displaced 30 Cu. Ft. cement thru  
DP from 340' to 265'. Pulled DP, set bridge @ 40' with 1 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Nichols  
Well Plugging Supervisor

FILED  
11/19/74  
322-W