

15-101-20002-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202RECEIVED
STATE CORPORATION COMMISSION
MAY 9 1969
CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Ronald Russ Prater,Complete Address: 501 Fourth National Bank Building, Wichita, Kansas.Lease Name Broun Well No. 1Location NE--SE-SW Sec. 36 Twp. 17 Rge. (E) (W) 27County Jane Total Depth 4570'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Forbes Casing Pulling Company,Address: Box #221, Grect Bend, Kansas. License No. 49Operation Completed: Hour 4:45PM Day 3 Month 5 Year 1969

The Above well was plugged as follows:

340'--8 5/8" Surface casing, cement circulated with 322 Sx.
4551'--4 3/8" Production casing cemented on bottom with 125 Sx. Open hole completion.Sanded well back to 4540' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing
and squeezed well with initially 5 sacks hulls and followed with 11 sacks gel then
100 Sx. cement from 975' to 650', then 7 sacks gel from 650' to 370' and followed
with 20 Sx. cement from 370' to 305' then 7 sacks gel from 305 to 30' and finally 10
Sx. cement from 30' to 0. Maximum pump-in pressure-350#. Final shut-in pressure-75#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Dinkel

Well Plugging Supervisor

DATE 5/9/69INV. NO. 9734-W