

15-101-20059-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 15 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling Company,
Complete Address Box #18407, Wichita, Kansas.
Lease Name Douglas Well No. 1
Location SW-NW-SW Sec. 13 Twp. 17 Rge. (E) (W) 27
County Jane Total Depth 4580'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Red Tiger Drilling Company,
Address 1720 Wichita Plaza, Wichita, Kans. License No.
Operation Completed: Hour 11:00 AM Day 12 Month 6 Year 1973

The above well was plugged as follows:

389'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 600'.

Circulated hole with heavy mud. Pulled DP to 825' and displaced 110 Cu. Ft. cement
thru DP from 825' to 500'. Pulled DP to 400' and displaced 30 Cu. Ft. cement thru DP
from 400' to 325'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 6/15/73
INV. NO. 4515-U