

15-101-20007-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 29 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Thunderbird Drilling & Petroleum Resources,  
Complete Address Box #18412, Wichita, Kansas.  
Lease Name Hagans Well No. E-1  
Location SE-NW Sec. 11 Twp. 17 Rge. (E) (W) 27  
County Lane Total Depth 4560'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated       
Plugging Contractor Sage Drilling Company, Incorporated,  
Address 500 Bitting Building, Wichita, Ks. License No.       
Operation Completed: Hour 10:30 PM Day 22 Month 12 Year 1970

The above well was plugged as follows:

329'--8 5/8" Surface casing, cement circulated with 235 Sx.  
Top of Dakota section @ 1075'.  
Circulated hole with heavy mud. Pulled DP to 1300' and displaced 100 Sx. cement thru  
DP from 1300' to 975'. Pulled DP to 320' and displaced 20 Sx. cement thru DP from  
320' to 160'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*  
Well Plugging Supervisor

INVOICED  
DATE 12/31/70  
INV. NO. 3137-W