



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 26 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Patrick Petroleum Corp.

Complete Address Suite 330 Page Court, 220 W. Douglas, Wichita, Kansas

Lease Name Nelson Well No. 1

Location C SW NE Sec. 25 Twp. 16 Rge. (E) (W) 25

County Ness Total Depth 4545'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Strata Drlg.

Address Wichita, Ks. License No.     

Operation Completed: Hour 7:30 P Day 20 Month 12 Year 1973

The above well was plugged as follows:

RTD 4545' 8 5/8 csg set at 284' cws 175 sx. Cem. Mat. 50-50 pez 6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 745' and displaced 70 sk cmt  
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru ~~drill~~  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INDEXED

DATE 12/28/73

INV. NO. 8344-W