

15-135-20006-0000

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 30 1967  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Sterling Drilling Company Inc.  
Complete Address: Box 129 Sterling Kansas  
Lease Name Flax Well No. 1  
Location C NW SW Sec. 25 Twp. 16 Rge. 25 (E)    (W) X  
County Ness Total Depth 1986'  
Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A X  
Other well as hereafter indicated:     
Plugging Contractor: Co. Tools  
Address:    License No.     
Operation Completed: Hour 4 P Day 26 Month 1 Year 1967

The Above well was plugged as follows:

RTD 1986' No csg set.  
Gunned pits, circulated heavy mud.  
Set 50 sc HA5 cement plug thru drill pipe, at 1635'. WOC 2 hrs. Top of cement 1535'  
Displaced 150 sc 50-50 pox cement 4% add. gel thru drill pipe, cementing 1525-1075  
Mud to 420'-Circulated thru drill pipe with 150 sc 50-50 pox cement 4% add. gel to  
base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: L. F. Mearns  
Well Plugging Supervisor

INVOICED  
DATE 1/30/67  
INV. NO. 4685-4