

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 116-31

LOCATION C. NW-SW

SEC. 23 TWP. 16 RGE. 15-W

Dry Hole  Abandoned Oil well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 2 Lease Holy Cross

Operator Sohio Petro Co. Address Bussell-Kans.

Field \_\_\_\_\_ County Ness

Total Depth 4568 Feet.

Plugging Contractor The West Supply Co

Plugging Contractor's License No. 14

Address Chase-Kans.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 334 ft. Circulated with cement  
5 1/2" casing set at 4539 ft. - 100 sacks of cement.  
Plugged back to 4500 ft with rock & sand - Dumped  
5 sacks of cement at 4500 ft. Shot off & pulled the  
5 1/2" casing - mud to 334 ft. - Set rock bridge &  
20 sacks of cement at 334 ft. - mud to 335 ft  
Plug & 10 sacks of cement at the surface.

RECEIVED  
STATE CORPORATION COMMISSION

AUG - 8 1953

C. D. Stough  
District Conservation Agent  
Wichita, Kansas  
Date 8-5-53

**PLUGGING**  
FILE SEC 23 T 16 R 250  
BOOK PAGE 116 LINE 31