

4
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sohio Oil Co
Complete Address: Box 673 Russell, Kans
Lease Name Holy Cross Well No. 1
Location CS. SW Sec. 23 Twp. 16 Rge. (E) (W) 25
County Ness Total Depth 4552
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Knight Casing Pulling
Address: Chase, Kans License No. 436
Operation Completed: Hour 2PM Day 4 Month 5 Year 65

The Above well was plugged as follows:

10" 313' circulated with cement - 5 1/2" 4550' Perf at 4417' squeezed at 1400' with 50 sax cement.

2 1/2" tubing cut off at 4000' - rerun tubing to 3977' spotted 5 sax cement through tubing at 3977' - pumped 10 sax mud through tubing at 3970' filling hole to 1600' with mud - shot off 5 1/2" at 1090' and pulled to 500' circulated hole with heavy mud through 5 1/2" at 500' (25 sax Gel) - displaced 25 sax cement through 5 1/2" at 500', heavy mud to 200', displaced 25 sax cement through 5 1/2" at 200', heavy mud to 30', set 10 sax cement to bottom cellar.

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edison Perry*
Well Plugging Supervisor

RECEIVED
5/7/65
INV. NO. 1110-W