

15-135-21132-00-00

R

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 5 1976

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brech
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Patrick Petroleum Corp.

Complete Address Suite 414, 200 E. First, Wichita, Kansas

Lease Name Giess "B" Well No. 1

Location C NW NE Sec. 26 Twp. 16 Rge. (E) (W) 25

County Ness Total Depth 4580'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor DNB Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 9 A Day 1 Month 1 Year 1976

The above well was plugged as follows:

RTD 4580' 8 5/8 csg set 317' cwc 180 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Murray
Well Plugging Supervisor

DATE 1-5-76

INV. NO. 2508-4