



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 6 - 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Okmar Oil Co.

Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name Wheat Well No. 1

Location C SE NE Sec. 17 Twp. 16 Rge. (E) (W) 25

County Ness Total Depth 4593'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 7:15 A Day 4 Month 5 Year 1974

The above well was plugged as follows:

RTD 4593' 8 5/8 csg set at 301' cwc 200 sk. Cmt. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Lawrence J. Massey  
Well Plugging Supervisor

DATE 5/2/74  
INV. NO. 9065-W