

15-135-21075-00-00



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Chief Drlg. Co.

Complete Address 905 Century Plaza, Wichita, Kansas

Lease Name Lynn-Pickering Well No. 1

Location C SE ~~SE~~ SW Sec. 19 Twp. 16 Rge. (E) (W) 25

County Ness Total Depth 4564'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 12:30 P Day 6 Month 8 Year 1975

The above well was plugged as follows:

RTD 4564' 8 5/8 csg set 275' cwc 200 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 750' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
AUG 8 1975
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Smalley
Well Plugging Supervisor

INVOICED
8/8/75
1745.4