



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED

OCT 27 1969

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Thunderbird Drilling, Inc.

Complete Address: 400 N. Woodlawn Wichita, Kansas

Lease Name Horacek Well No. 1

Location Approx. C NW NE Sec. 19 Twp. 16 Rge.      (E)      (W) 25

County Ness Total Depth 4565

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Dunne - Gardner

Address: Wichita, Kansas License No.     

Operation Completed: Hour 10:15A Day 26 Month 10 Year 1969

The Above well was plugged as follows:

RTD 4565' 8 5/8 csg set at 333' cwc 225 sk. Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 900' and displaced 70 sk cmt.

thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED  
10/27/69  
732-W

Signed: Leo J. Massey  
Well Plugging Supervisor