

15-135-20338-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 18 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drlg. Co., Inc.

Complete Address Suite 905 Century Plaza, Wichita, Kansas

Lease Name Ruthrauff Well No. 1

Location SE NW Sec. 20 Twp. 16 Rge. (E) (W) 25

County Ness Total Depth 4566'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 3:45P Day 14 Month 5 Year 1970

The above well was plugged as follows:

RTD 4566' 8 5/8 csg set at 290' cwc Cmt. at. 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 900' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulle and 10 sk cmt to

base of collar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 5/22/70
INV. NO. 1919-12